

ADDENDUM ONE

Project: Exterior Waterproofing and Roof Repairs
Landis Hall
Florida State University

March 18, 2013

This addendum forms a part of the contract documents and modifies the original specifications and drawings, dated January 13, 2012, as noted below. Acknowledge receipt of the Addendum in the space provided on the proposal form. Failure to do so may subject Bidder to disqualification.

ITEM NO. 1 – PREBID MEETING AND PREQUALIFIED BIDDERS

The mandatory prebid meeting was held on March 19, 2013 at 10:00 am. The following contractors attended the mandatory prebid meeting and are the only qualified contractor to bid this project:

Rowe Roofing
Jenkins Roofing
Harrell Roofing
Old World Roofing

ITEM NO. 2 – PREBID MEETING

Clarification: Bid opening to be on March 28th at 2:00 pm.

ITEM NO. 3 – PROJECT MANUAL, SECTION 01010, SUMMARY OF WORK

Change: Abbreviated Written Summary: The reroofing and gutter replacement work of the Shores Building, at Florida State University includes; carefully removing the existing roof tiles to be salvaged for reinstallation, removing underlayment and felts from the steep sloped roofs indicated down to the wood deck, and removing the copper clad modified bitumen membrane gutter roofing system, parapet wall base flashing, tapered insulation down to the existing structural wood deck of the built-in gutter. The work includes installation of new rubberized waterproofing membrane underlayment, and reinstallation of salvaged roof tiles and new roof tiles to match. It also includes installing a new tapered insulation roofing system, and mineral surface modified bitumen membrane roofing and flashing system in the built-in gutter areas indicated.

END OF ADDENDUM ONE